

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

Company: SUMMIT PETROLEUM
Name:
ClientProj: 2020704031
GTA ProjNo: 022621-4

Site Addr: RUCK

Sampled By: MAX KORNDORFER/GCES
Date Rec: 2/26/2021
Time Rec: 12:52 PM

Sample No.	Sample ID	Date Sampled	Time Sampled	Sample Matrix
1	HA-11 (0.5')	2/25/2021	11:05 AM	SOIL
2	HA-12 (0.5')	2/25/2021	11:15 AM	SOIL
3	HA-13 (1')	2/25/2021	11:30 AM	SOIL
4	HA-14 (1')	2/25/2021	11:45 AM	SOIL
5	HA-15 (1')	2/25/2021	12:15 PM	SOIL
6	HA-16 (2')	2/25/2021	12:35 PM	SOIL
7	HA-17 (1')	2/25/2021	1:00 PM	SOIL
8	HA-18 (1')	2/25/2021	1:40 PM	SOIL

ELECTRONIC SIGNATURE REPORT. This is a final report for the following pages of data for the samples specified above. All analysis was performed by the methods stated and all quality control measures required were completed. All quality control information is available upon request.

Kirk Chase

Kirk L. Chase/Chemist
Grand Traverse Analytical
830 Robinwood Court
Traverse City, MI 49686
Ph: 231-929-0905
Fx: 231-929-0894
SP: 231-590-0291
kirk@gtanalytical.com

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

MI

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-11 (0.5')

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 1

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:05 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	ND	50	ug/Kg (PPB)	MR	2/25/2021	3/2/2021	EPA 5035A
Toluene	ND	50					
Ethylbenzene	ND	50					
Xylene(Total)	ND	150					
1,2,4-Trimethylbenzene	ND	50					
1,3,5-Trimethylbenzene	ND	50					
Naphthalene	ND	250					
2-Methylnaphthalene	ND	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

MI

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-12 (0.5')

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 2

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:15 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	ND	50	ug/Kg (PPB) MR		2/25/2021	3/2/2021	EPA 5035A
Toluene	ND	50					
Ethylbenzene	ND	50					
Xylene(Total)	ND	150					
1,2,4-Trimethylbenzene	ND	50					
1,3,5-Trimethylbenzene	ND	50					
Naphthalene	ND	250					
2-Methylnaphthalene	ND	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

MI

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-13 (1')

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 3

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:30 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	140	50	ug/Kg (PPB)	MR	2/25/2021	3/3/2021	EPA 5035A
Toluene	200	50					
Ethylbenzene	140	50					
Xylene(Total)	430	150					
1,2,4-Trimethylbenzene	130	50					
1,3,5-Trimethylbenzene	120	50					
Naphthalene	ND	250					
2-Methylnaphthalene	ND	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

MI

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-14 (1')

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 4

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:45 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	680	60	ug/Kg (PPB)	MR	2/25/2021	3/3/2021	EPA 5035A
Toluene	540	60					
Ethylbenzene	7,000	600					
Xylene(Total)	27,000	1,800					
1,2,4-Trimethylbenzene	12,000	600					
1,3,5-Trimethylbenzene	4,700	60					
Naphthalene	5,200	250					
2-Methylnaphthalene	6,900	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

PROJECT NO: 2020704031

GTA SAMPLE NO: 5

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 12:15 PM

MI

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-15 (1')

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	ND	50	ug/Kg (PPB) MR		2/25/2021	3/3/2021	EPA 5035A
Toluene	78	50					
Ethylbenzene	ND	50					
Xylene(Total)	1,200	150					
1,2,4-Trimethylbenzene	700	50					
1,3,5-Trimethylbenzene	1,000	50					
Naphthalene	810	250					
2-Methylnaphthalene	1,000	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

PROJECT NO: 2020704031

GTA SAMPLE NO: 6

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 12:35 PM

MI

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-16 (2')

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	ND	50	ug/Kg (PPB) MR		2/25/2021	3/2/2021	EPA 5035A
Toluene	ND	50					
Ethylbenzene	ND	50					
Xylene(Total)	ND	150					
1,2,4-Trimethylbenzene	ND	50					
1,3,5-Trimethylbenzene	ND	50					
Naphthalene	ND	250					
2-Methylnaphthalene	ND	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

PROJECT NO: 2020704031

GTA SAMPLE NO: 7

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 1:00 PM

MI

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-17 (1')

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	ND	50	ug/Kg (PPB) MR		2/25/2021	3/2/2021	EPA 5035A
Toluene	ND	50					
Ethylbenzene	ND	50					
Xylene(Total)	ND	150					
1,2,4-Trimethylbenzene	ND	50					
1,3,5-Trimethylbenzene	ND	50					
Naphthalene	ND	250					
2-Methylnaphthalene	ND	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

MI

SAMPLE MATRIX: SOIL

SAMPLE ID: HA-18 (1')

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 8

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 1:40 PM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

SAMPLED BY: MAX KORNDORFER/GCES

**THIS SAMPLE WAS RECEIVED MEOH PRESERVED.

EPA 8260B VOLATILE ORGANICS

<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date</u> <u>Extracted</u>	<u>Date</u> <u>Complete</u>	<u>Prep Method</u>
Benzene	ND	50	ug/Kg (PPB) MR		2/25/2021	3/3/2021	EPA 5035A
Toluene	ND	50					
Ethylbenzene	ND	50					
Xylene(Total)	ND	150					
1,2,4-Trimethylbenzene	ND	50					
1,3,5-Trimethylbenzene	ND	50					
Naphthalene	ND	250					
2-Methylnaphthalene	ND	250					

SOIL/SOLIDS CONCENTRATIONS ARE DETERMINED ON A DRY WEIGHT BASIS.

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 1

PROJECT NO: 2020704031

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:05 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS**No: Analysis**

SAMPLE ID: HA-11 (0.5')

CHLORIDE EPA 300.0

Concentration

ND

LOD

120

Units

mg/Kg (PPM) LV

Analyst

LV

Date Completed

3/2/2021

Sample

SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 2

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:15 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS**No: Analysis**

SAMPLE ID: HA-12 (0.5')

CHLORIDE EPA 300.0

Concentration

ND

LOD

120

Units

mg/Kg (PPM) LV

Analyst

LV

Date Completed

3/2/2021

Sample

SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 3

PROJECT NO: 2020704031

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:30 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS

<u>No:</u>	<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date Completed</u>	<u>Sample</u>
	SAMPLE ID: HA-13 (1')						
	CHLORIDE EPA 300.0	ND	120	mg/Kg (PPM)	LV	3/2/2021	SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

PROJECT NO: 2020704031

GTA SAMPLE NO: 4

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:45 AM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS

<u>No:</u>	<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date Completed</u>	<u>Sample</u>
	SAMPLE ID: HA-14 (1')						
	CHLORIDE EPA 300.0	ND	120	mg/Kg (PPM)	LV	3/2/2021	SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

COMPANY: SUMMIT PETROLEUM
PROJECT NO: 2020704031
LOCATION: RUCK

MI
SAMPLED BY: MAX KORNDORFER/GCES

GTA PROJECT NO: 022621-4
GTA SAMPLE NO: 5

DATE SAMPLED: 2/25/2021
TIME SAMPLED: 12:15 PM
DATE RECEIVED: 2/26/2021
TIME RECEIVED: 12:52 PM

SAMPLE ANALYSIS

<u>No:</u>	<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date Completed</u>	<u>Sample</u>
	SAMPLE ID: HA-15 (1')						
	CHLORIDE EPA 300.0	ND	120	mg/Kg (PPM)	LV	3/2/2021	SOIL

ND = NOT DETECTED, RESULT < LOD
LOD = LIMIT OF DETECTION
s.u. = STANDARD pH UNITS REPORTED AT 25 C

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

PROJECT NO: 2020704031

GTA SAMPLE NO: 6

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 12:35 PM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS

<u>No:</u>	<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date Completed</u>	<u>Sample</u>
	SAMPLE ID: HA-16 (2')						
	CHLORIDE EPA 300.0	ND	120	mg/Kg (PPM)	LV	3/2/2021	SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

COMPANY: SUMMIT PETROLEUM

PROJECT NO: 2020704031

LOCATION: RUCK

GTA PROJECT NO: 022621-4

GTA SAMPLE NO: 7

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 1:00 PM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS

<u>No:</u>	<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date Completed</u>	<u>Sample</u>
	SAMPLE ID: HA-17 (1')						
	CHLORIDE EPA 300.0	ND	120	mg/Kg (PPM)	LV	3/2/2021	SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

GTA PROJECT NO: 022621-4

PROJECT NO: 2020704031

GTA SAMPLE NO: 8

LOCATION: RUCK

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 1:40 PM

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MI

SAMPLED BY: MAX KORNDORFER/GCES

SAMPLE ANALYSIS**No: Analysis**

SAMPLE ID: HA-18 (1')

CHLORIDE EPA 300.0

Concentration

ND

LOD

110

Units

mg/Kg (PPM) LV

Analyst

LV

Date Completed

3/2/2021

Sample

SOIL

ND = NOT DETECTED, RESULT < LOD

LOD = LIMIT OF DETECTION

s.u. = STANDARD pH UNITS REPORTED AT 25 C

**INDEPENDENT TESTING LAB**

830 ROBINWOOD COURT, TRAVERSE CITY, MI 49686

PH: 231-929-0905

FAX: 231-929-0894

www.gtanalytical.com

COMPANY: SUMMIT PETROLEUM

NAME:

PROJECT NO: 2020704031

LOCATION: RUCK

MI

GTA PROJECT NO: 022621-

SAMPLED BY: MAX KORNDORFER/GCES

DATE SAMPLED: 2/25/2021

TIME SAMPLED: 11:05 AM

SAMPLE MATRIX: SOIL

DATE RECEIVED: 2/26/2021

TIME RECEIVED: 12:52 PM

MOISTURE

<u>No:</u>	<u>Analysis</u>	<u>Concentration</u>	<u>LOD</u>	<u>Units</u>	<u>Analyst</u>	<u>Date Completed</u>
SAMPLE ID: HA-11 (0.5')	% MOISTURE EPA 3550C	16	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-12 (0.5')	% MOISTURE EPA 3550C	18	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-13 (1')	% MOISTURE EPA 3550C	18	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-14 (1')	% MOISTURE EPA 3550C	18	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-15 (1')	% MOISTURE EPA 3550C	16	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-16 (2')	% MOISTURE EPA 3550C	17	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-17 (1')	% MOISTURE EPA 3550C	18	0.050	% OF SAMPLE	AS	2/26/2021
SAMPLE ID: HA-18 (1')	% MOISTURE EPA 3550C	14	0.050	% OF SAMPLE	AS	2/26/2021

CHAIN OF CUSTODY

PROJECT NUMBER 2020704031	SITE NAME/ADDRESS Ruck	COMPANY/NAME Summit Petroleum
SAMPLED BY M. Krodarfer	COMPANY Gces	GTA PROJECT # 022621-4

SAMPLE INFORMATION

#	SAMPLE ID	DATE SAMPLED	TIME	MATRIX	ANALYSIS
1	HA-11 (0.5')	2-25-21	11:05	Soil	BTEX + 4, Chloride
2	HA-12 (0.5')	↑	11:15	↑	↑
3	HA-13 (1')	↑	11:30	↑	↑
4	HA-14 (1')	↑	11:45	↑	↑
5	HA-15 (1')	↑	12:15	↑	↑
6	HA-16 (2')	↑	12:35	↑	↑
7	HA-17 (1')	↓	1:00	↓	↓
8	HA-18 (1')	2-25-21	1:40	Soil	BTEX + 4, Chloride

BILL TO:

Summit Petroleum

REPORT TO:

Eric Vincke (Gces)
Laura Dylce (Summit)

RELEASED BY

DATE/TIME

[Signature]

2-26-21 12:52

RECEIVED BY

DATE/TIME

[Signature] 2/26/21 12:52

REQUESTED TAT

☐ STANDARD

☐ 1 BUSINESS DAY

☐ 2 BUSINESS DAYS

☐ 3 BUSINESS DAYS